
STATE OF CONNECTICUT

OFFICE OF LEGISLATIVE MANAGEMENT



CONNECTICUT'S OLD STATE HOUSE ROOF REPLACEMENT AND EXTERIOR RENOVATIONS

800 MAIN STREET HARTFORD, CONNECTICUT 06106

PROJECT CT 7301 APRIL 13, 2012 ISSUED FOR BIDDING

ARCHITECT OF RECORD:



TectonArchitects | inc

ONE HARTFORD SQUARE WEST HARTFORD CONNECTICUT TEL 860 548 0802 FAX 860 249 2531 www.tectonarchitects.com

JOB NO. CT-7301

CONTRACT DRAWINGS

NO. TITLE

ARCHITECTURAL

COVER COVER SHEET A-101 DEMOLITION ROOF PLAN

A-201 ROOF CONSTRUCTION PLAN A-202 REFLECTED ROOF EAVE PLAN

A-301 EXTERIOR ELEVATIONS A-302 EXTERIOR ELEVATIONS

A-302 EXTERIOR ELEVATIONS
A-303 EXTERIOR ELEVATIONS

A-501 ENLARGED BALUSTRADE ELEVATIONS A-502 ENLARGED CUPOLA ELEVATIONS

A-601 DETAILS A-602 DETAILS

ELECTRICAL E-001 ELECTRICAL GENERAL NOTES & ABE

E-001 ELECTRICAL GENERAL NOTES & ABBREVIATIONS
ED-101 ROOF ELECTRICAL DEMOLITION PLAN

ED-101 ROOF ELECTRICAL DEMOLITION PLAN E-101 ROOF ELECTRICAL PLAN

E-102 ATTIC ELECTRICAL PLANS E-201 ELECTRICAL PARTIAL PLANS

BUILDING CODE INFORMATION

SCOPE OF WORK: THIS PROJECT ENTAILS THE REPAIR
AND HISTORIC RESTORATION OF THE FACADES AND
ROOF OF THE EXISTING OLD STATE HOUSE. THERE IS NO

OCCUPANCY A-3: ASSEMBLY (EXIST./UNCHG.) CLASSIFICATION:

TYPE OF 2C (CSBC 602.0) EXIST. UNCHG. CONSTRUCTION: II (000) (LIFE SAFETY CODE)


HEIGHT & AREA: EXIST. UNCHG.

OCCUPANCY: 1100P. - EXISTING UNCHANGED

CODE DATA BASED UPON INFORMATION GATHERED FROM BASEMENT GALLERY PROJECT (c. 2005) BY DBA. REFERENCE CODES ARE THE 2000 CSBC SERIES OF DOCUMENTS.

BUILDING

CONNECTICUT'S OLD STATE HOUSE





PROJECT LOCATION

GENERAL DESCRIPTION OF THE WORK SCOPE INCLUDES:

 REMOVAL OF THE EXISTING BALUSTRADES & POSTS FOR REBUILDING OF THE POSTS AND RESTORATION OF THE BALUSTERS & RAILS. REINSTALL ALL BALUSTRADES.
 REMOVAL AND DISPOSAL OF EXISTING SLATE ROOFING

AND ALL ASSOCIATED FLASHINGS.
REMOVAL OF COPPER GUTTER LININGS AND LEADERS.
RESTORATION AND PAINTING OF ALL WOOD EAVE COMPONENTS, INCLUDING MUTULES, TRIMS, PEDIMENTS & BEAMS, COLUMN CAPS, SOFFITS. THIS INVOLVES

WORKING WITH LEAD-BASED PAINT.
 NEW COPPER GUTTER LININGS & LEADERS, NEW COPPER FLAT SEAM ROOFING AT EAVE TO ABOUT 4 FEET ABOVE

THE BALUSTERS.
NEW SLATE ROOFING INCLUDING ALL NEW BASE FLASHINGS AND PLYWOOD DECKING OVERLAY.
REPLACEMENT OF PAINTED TIN SIDING AT CUPOLA

REPLACEMENT OF PAINTED TIN SIDING AT CUPOLA BASE.
 STONE RESTORATION OF SELECTED BROWNSTONE THAT INCLUDES BOTH SURFACE RESTORATION UTILIZING REPAIR PRODUCTS AND APPLYING NEW STONE

DUTCHMEN FACINGS TO EXISTING STONE.
 LIMITED OTHER MASONRY REPAIRS, BUT ONLY THAT REQUIRED TO PERFORM THE REPAIRS - A COMPLETE MASONRY RESTORATION / CLEANING / REPOINTING OF

THE BUILDING IS NOT PART OF THIS PROJECT.
NEW ELECTRICAL TO INCLUDE CUPOLA LIGHTING, ROOFTOP POWER FOR HOLIDAY LIGHTS AND RAIN

LEADER HEAT TRACING (TRACING SYSTEM BY OWNER).

• ALTERNATE 1 FOR RESTORATION OF EAST LOGGIA STONE STEPS.

APPROVALS

AGENCY

DATE

DATE

